



TheCounty
PRINCE EDWARD COUNTY • ONTARIO

CORPORATION OF THE COUNTY OF PRINCE EDWARD
CONTRACT NO. 2018-EDW-08 WILSON ROAD REHABILITATION

ADDENDUM NO. 2

ISSUED: April 12th, 2018

This addendum is issued prior to receipt of tenders and shall amend and/or clarify the work as follows:

1. The following new provisional item has been added to the contract and may replace other disposal items as may be appropriate during construction. A revised tender table is attached.

Provisional Item 30 Hauling And Disposal Of Excess Excavated Material To County Site

Payment at the unit price for this item shall be full compensation for the hauling and disposal of excess excavated material, to a County owned disposal site located within a 30 km. radius of the Wilson Road project site. The Contractor shall be fully responsible to ensure that the transportation of the excess excavated material to the County site is carried out in accordance with current Provincial regulations and guidelines. The Contractor will not be responsible for undertaking any additional sampling and laboratory testing to ensure that the disposal and management of the excess materials at the County site is carried out in accordance with the Provincial regulations and guidelines.

Where possible, excavated material is to be used on site to minimize the amount of material required for offsite disposal.

Payment shall be by the cubic metre which shall be based on a capacity for each vehicle used by the Contractor for the transportation to the disposal site established by the Contract Administrator in consultation with the Contractor.

End of Addendum

(A signed copy of this addendum is to be included in Tender submission.)

I /WE hereby acknowledge receipt of this addendum.

Signed (must be Signing Officer of Firm)

Position

Name of Firm

| Item | OPSS | DESCRIPTION | UNIT | QTY. | Unit Cost | Total Cost |
|-----------------------------|-------------------------|---|----------------|--------|------------------|------------|
| ROAD / SURFACE WORKS | | | | | | |
| 1 | SP | Mobilization and Demobilization | L.S. | 1 | | |
| 2 | SP, 180, 201 | Clearing (Close Cut) | m | 1,386 | | |
| 3 | SP, 706 | Traffic Control | L.S. | 1 | | |
| 4 | SP, 805 | Environmental Protection | L.S. | 1 | | |
| 5 | SP, 206, 510 | Excavation and Removals (Road Widening) | m | 7,070 | | |
| 6 | SP, 206, 510 | Excavation and Removals (Shallow Ditch/Cleanout) | m | 954 | | |
| 7 | SP, 206, 510 | Excavation and Removals (New Ditching) | m | 643 | | |
| 8 | SP, 206, 510 | Hauling and Disposal of Excavated Material | tonne | 8,781 | | |
| 9 | SP, 314, 501, 1010 | Granular A (Road Widening) | tonne | 2,672 | | |
| 10 | SP, 314, 501, 1010 | Granular A (100mm Fine Grading) | tonne | 5,523 | | |
| 11 | SP, 314, 501, 1010 | Granular A (Shoulders) | tonne | 267 | | |
| 12 | - | Pulverizing (100mm) | m ² | 18,774 | | |
| 13 | SP, 308, 310, 1150 | Surface Coarse Asphalt (50mm) | tonne | 2,928 | | |
| 14 | SP, 510, 517, 518, 1013 | 400mm CSP Cross Culvert | m | 28 | | |
| 15 | SP, 510, 517, 518, 1013 | 450mm CSP Cross Culvert | m | 39 | | |
| 16 | SP, 510, 517, 518, 1013 | 500mm CSP Cross Culvert | m | 11 | | |
| 17 | SP, 510, 517, 518, 1013 | 450mm CSP Entrance Culvert | m | 24 | | |
| 18 | SP, 510, 517, 518, 1013 | 300mm CSP Entrance Culvert | m | 9 | | |
| 19 | SP, 710, 1716 | Water Borne Pavement Markings | L.S. | 1 | | |
| 20 | SP, 703 | Signage/Mailbox Relocations | L.S. | 1 | | |
| | | | | | Subtotal | |
| PROVISIONAL WORKS | | | | | | |
| 21 | SP, 802 | Topsoil and Hydroseed | m ² | 8,501 | | |
| 22 | SP, 802 | Topsoil and Sod | m ² | 1,080 | | |
| 23 | SP, 308, 310, 1150 | Miscellaneous Asphalt (HL-3) | tonne | 47 | | |
| 24 | SP, 510 | Tree Removal (100mm to 300mm) | Ea. | 15 | | |
| 25 | SP, 314, 501, 1010 | Granular B (Road Subbase) | tonne | 682 | | |
| 26 | SP, 314, 501, 1011 | Granular A (Road Base) | tonne | 409 | | |
| 27 | SP, 405 | 150mm Subdrain | m | 200 | | |
| 28 | - | Culvert Inlet/Embankment Protection | ea. | 2 | | |
| 29 | - | Hydro Pole Protection | ea. | 6 | | |
| 30 | SP, 206, 510 | Hauling and Disposal of Excavated Material to County Site | tonne | 8,781 | | |
| | | | | | Subtotal: | |

Subtotal of All Work:

HST:

Total:
